

2.6.2.5 Horizontal termination

Horizontal terminations shall not be used in any situation.


NOTE: The correct method is to continue the membrane to an edge and terminate it on a vertical surface.

2.6.3 Doors and windows onto external waterproofed areas

2.6.3.1 Membrane installation

Membranes shall be installed prior to the fixing of door or window frames (see Figures 2.8 and 2.9).

There is to be no vertical fixing through the horizontal surface sill/subsill of the door. If the door is sufficient length that it requires horizontal restraint along its length, this fixing shall be done horizontally to an angle behind the door sill/subsill.



NOTE: For falls, see Clause 2.4.1.

FIGURE 2.8 DETAIL OF MEMBRANE TERMINATION AT EXTERNAL OPENINGS DOORS